Maryland Transit Administration

ONGOING IMPROVEMENTS

MTA Maryland

Here's how our work to make your ride better might affect your travel plans.

The Maryland Transit Administration works continuously to maintain and improve our infrastructure and facilities statewide. Here are the projects we're working on that are most likely to have an impact on the traveling public this month.

May 2015

MARC TRAIN

Odenton Station Miscellaneous Improvements

DESCRIPTION: Repair to asphalt pavement, concrete sidewalk, curb and gutter, and accessible ramps; updates to ADA accessible parking signs and fabrication and installation of way finding signage within the parking lots, boarding platforms, and pedestrian pathways.

IMPACT: Work that will directly have an impact on customer access or parking facilities will be completed on weekends and off-peak hours.

West Baltimore MARC Station Beautification, Parking Expansion

DESCRIPTION: This project attaches art work to the light poles that were constructed as part of the parking expansion and adds plaques to recognize contributions by significant past community leaders.

IMPACT: Installation of the art work will be scheduled to minimize its impact on MARC customers. Work area will be located in the newly created lots C & D.

Monocacy Station Park and Ride Lot Repairs

DESCRIPTION: This project includes repairing & replacing areas of concrete sidewalk and ADA ramps, installation of bollards and new pavement markings for ADA accessible parking, milling and new 2" asphalt overlay of the entire parking lot and entry road, and new line striping throughout the lot.

IMPACT: ome minor work will be taking place during the week between 9am and 3pm but otherwise all work will be taking place on weekends while this station is closed in order to minimize customer impact.

COMMUTER BUS

Construction of new Waldorf Park and Ride Facility

DESCRIPTION: : Roadway widening along Old Washington Road, construction of a new signal at the roadway intersection and construction of a new 484-vehicle park and ride facility.

IMPACT: Roadway widening and signal work will affect traffic on Smallwood Drive and Old Washington Road. The right turn lane on Smallwood Drive is closed. The impact will be minimal and traffic is expected to move smoothly.

LIGHT RAIL / MARC TRAIN

Homeland Security CCTV Phase IV

DESCRIPTION: Install high resolution surveillance cameras to monitor and record activity associated with rail platforms. The cameras are viewable by the MTA Police in real-time. The addition of the cameras will enhance public safety and security at various rail stations; including including MARC College Park, Penn Station, and West Baltimore.

IMPACT: Construction occurring on platforms is scheduled to minimize impact on customers.

LIGHT RAIL / MARC TRAIN/ METRO SUBWAY

AGY EV Charger Installation

DESCRIPTION: Install new dual electric car chargers at the following MTA modal parking facilities: MARC – Halethorpe, Monocacy, Muirkirk and West Baltimore / LIGHT RAIL – Lutherville, North Linthicum and Cromwell Station / METRO – Milford Mill.

IMPACT: Construction occurring on platforms is scheduled to minimize impact on customers.

Repairs to Freight Rail Line Structures Statewide

DESCRIPTION: Remove wearing surface on bridge 13.55 at intersection of High Bridge Road and Glanding Road in Queen Anne's County.

IMPACT: The intersection will be closed for a few weeks while work is performed and paving occurs, a detour will re-direct traffic.